









Project History

- CBD Loop Arterial Location Study (1979)
- MLK Jr. Parkway EIS (1987)
- Supplemental EIS (1999)
- SE Diagonal Corridor Study (1999)
- MLK Re-eval of EIS (2007)*
- SE Connector EIS (2010)*



Project Need



Enhanced Mobility, Access And Opportunity

The Southeast Connector will result in an efficient, direct access corridor to address the mobility needs of this quadrant of Des Moines and the broader metropolitan area. Improvements will increase access to existing neighborhoods, business and industry, as well as facilitate future developments, such as the Agrimergent Technology Park.



Roadway Capacity

Traffic projections predict that by 2030 the current road network will be unable to accommodate expected traffic levels. Without investment in the corridor, travelers would likely have to divert to a longer and less efficient route that could compromise economic competitiveness.




Economic Revitalization And Goods Movement


The SE Connector will provide economic redevelopment opportunities for the area southeast of the Central Business District and will improve goods movement for existing and future truck traffic throughout the City of Des Moines.




System Connectivity Improvements


The Southeast Connector will provide Des Moines' southeast side with a direct, safe and efficient link to the downtown and the broader regional transportation system.























Final Design Challenges & Solutions

- Sunset Beach Lake
- Lime Pile (Mountain)
- Mulch/Plastic Stockpile
- Rubble Relocation
- USACE Levee Relocation
- Railroad Stoplog Closure
- Bridge over Fourmile Creek & Rail Spur

DES MOINES
KIRKHAM
MICHAEL

Sunset Beach Lake



- Former Sand Quarry
- 22' deep in the middle
- Former Swimming Area
- \$2 M to fill



Sunset Beach Lake - Solution

- Saved \$2M by building the north lanes instead of the south lanes through this section of the project.
- Pond is city-owned and can be filled by other future projects with excess soil.
- Full-Build not needed until 2050 based on Traffic Study




Lime Pile (Mountain) Relocation



- 163,000 CY Relocation
- 500,000 CY pile, 95' high
- Byproduct of DMWW








Mulch/Plastic Pile Removal



Mulch/Plastic Pile- Solution




Rubble Relocation




Rubble Relocation- Solution

- All removed material to be used as unsuitable fill beneath deeper fill zones
- Complies with Std. Road Plan EW-102 placement
- Material required to be free of all debris/trash
- Saved estimated \$500,000 by not hauling off-site and finding more borrow material.




USACE Levee Relocation



New Levee Solution


- Included in project to take advantage of mass earthwork pricing
- Set separately from roadway so USACE can be owner / operator
- Separate levee can be raised independently of roadway
- Saved estimated \$400,000 by including in the project.




Railroad Stoplog Closure




- Existing Structure Constructed in 2010
- Concrete Stoplogs
- Requires train car & crane
- Major Liability for Flash-Flooding
- Line of protection raised by 18-inches







Stoplog Closure- Solution

- Retrofit of existing structure to raise to new elevation.
- Stop-Logs redesign to aluminum logs with center brace.
- Storage wall designed on-site to decrease response time.
- Requires 24-hour removal of tracks.












Fourmile Creek - Bridge





Fourmile Creek - Bridge





Fourmile Creek - Bridge




















Fourmile Creek - Bridge




Fourmile Creek - Bridge





Fourmil











Project Quantities

• Clearing & Grubbing:	57 Acres
• Earthwork:	465,000 CY
• Modified Subbase:	37,000 CY
• Storm Sewer:	4.3 Miles
• 10" PCC Paving:	87,000 SY
• Sidewalk/Trail:	3.6 Miles
• Lime Pile Relocation:	163,000 CY
• Trash Pile Removal:	22,000 CY
• Fencing:	5.03 Miles
• Bridge Length:	1,515 LF
• Total Bid Items:	255

KIRKHAM MICHAEL

Special Provisions (16)


Special Provisions:

- Levee Closeout Procedures
- Sluice Gates (Gatewell)
- Flood Contingency Plan
- Landus Railroad
- Levee Construction
- Manhole Epoxy Liner
- NPDES
- Roadway Electrical
- Roadway Lighting
- Roadway Electrical
- Stoplog Closure
- Traffic Signs
- Traffic Signalization
- Tree Protection
- Water Mains
- Norfolk Southern Railway

IOWA DOT


KIRKHAM MICHAEL


- Progress Schedule
- Modular Expansion Joint Assembly
- Girder Erection Plan
- Mass Concrete
- Electronic Ticketing
- BNSF Railway
- PCC Pavement Non-Destructive Thickness Determination
- High Performance Concrete for Structures
- Fiber Reinforcement for Structural Concrete
- DBE Trucking



- **10 Project Stages**
 - 6 Stages for SE 30th
- **8 Completion Provision Sites w/ penalties:**
 - E. MLK & SE 36th Street – as detour
 - SE 36th Street – **DART bus barn**
 - Railroad Track – **Stoptop Closure**
 - SE 30th Street - Four sites







Funding


Applied for multiple Grants to fund \$60M budget

- Submitted for several years to RAISE Grant
- \$34.0M Infrastructure for Rebuilding America (INRFA) Grant
- \$11.3M Federal Surface Transportation Program (STP)
- \$13.7M City Funds

Source	Amount
INRFA Grant	\$34.0 M
STP	\$11.3 M
City Funds	\$13.7 M
Total	\$60.0 M




















Project Website: www.seconnector.com



Project Flyover



Questions?

Contact:
Scott Almeida, P.E., Vice President
Kirkham Michael & Associates
salmeida@kirkham.com