

I-35/80 & US6 (Hickman Road) Interchange Reconstruction

ACEC

Nathan Carhoff, Snyder & Associates

Matthew Cushman, Terracon

Garret Menard, HDR

Frank Leong, Iowa DOT





September 26, 2025

Project Stat Sheet



Interstate System

- Total 2.6 Miles (0.5 Mile Reconstruction)
- 12 Lane Roadway Section
- 5 Thru & 1 Auxiliary Lane Each Direction
- Widen Walnut Creek Bridge(s)
- Grade Separated Pedestrian Facilities
- 4,400 LF MSE Walls


Hickman Road

- Total 0.8 Miles Reconstruction
- 8 Lane Roadway Section
- 5 Thru & 1 Auxiliary Lane Each Direction
- Replace Hickman Bridge(s)
- Extensive Utility Relocation
- 1,900 LF Soil Nail Walls




Project Stat Sheet

\$138,000,000 Total Project Cost	\$11,500,000 Local Participation
430,000 CY Earthwork	220,000 SY Pavement
12,000 LF Storm Sewer	160 Storm Sewer Structures
5,900 CY Structural Concrete	6,028,000 LB Structural Steel
23,500 LF Pile	47,000 LF ITS Conduit
27 Miles of Temporary Barrier Rail	4-Year Construction Timeline



Project Need

[illegible]

Project Need:

[illegible][illegible]


Roadway / Interchange Design




Image Courtesy of Google Earth - 2024

[illegible]


Roadway / Interchange Design





Roadway / Interchange Design




Roadway / Interchange Design












Structural Design: Hickman Bridge



Structural Design: Hickman Bridge




Structural Design: Hickman Bridge






Structural Design: Walnut Creek Bridge



Structural Steel Framing Plan




Structural Design: Walnut Creek Bridge



Section Thru Erosion Stone And Embedded Revetment Berm



Bicycle / Pedestrian Accommodations




[illegible][illegible]

Landscaping & Aesthetics



Landscaping & Aesthetics



Landscaping & Aesthetics




Landscaping & Aesthetics



SNYDER
ASSOCIATES

Landscaping & Aesthetics



SNYDER
ASSOCIATES




Landscaping & Aesthetics



SNYDER
ASSOCIATES

Landscaping & Aesthetics



MSE WALL D1 AESTHETIC DETAILS

SNYDER
ASSOCIATES



Landscaping & Aesthetics




SNYDER
ASSOCIATES

Landscaping & Aesthetics



SNYDER
ASSOCIATES

Landscaping & Aesthetics




SNYDER
ASSOCIATES


















Geotechnical Challenges

I-35/80 & Hickman Road Interchange

2025 ACEC-IA + Iowa DOT + FHWA
Iowa Transportation Conference

Presented by
Matthew D. Cushman, P.E.
September 26, 2025

Terracon
Engineers with art

Geotechnical Challenges I-35/80 & Hickman Road Interchange

- Soils remediation is driven by the need to improve on-site conditions to meet project requirements



Explore with us

Geotechnical Challenges I-35/80 & Hickman Road Interchange

- Soils remediation is driven by the need to improve on-site conditions to meet project requirements
- While this project includes 'typical' geotechnical solutions, like
 - Granular blankets in low-lying wet areas
 - IFIs (stone columns, aggregate piers) below retaining walls
 - Subdrains to remove water




Explore with us


Geotechnical Challenges I-35/80 & Hickman Road Interchange


- Soils remediation is driven by the need to improve on-site conditions to meet project requirements
- While this project includes 'typical' geotechnical solutions, like
 - Granular blankets in low-lying wet areas
 - IFIs (stone columns, aggregate piers) below retaining walls
 - Subdrains to remove water
- How we addressed downdrag at three bridge locations and our project successes (from my perspective)



Explore with us








I-35 NB/I-80 EB at Walnut Creek

Alluvial Clays, Typical Properties

- γ_t (pcf): 120 to 125
- %m: 27 to 32
- N-Values: 4 to 7
- $\frac{1}{2}Q_u$ (psf): 300 to 700
- s_u (psf): 250 to 350
- LL: 38 to 43
- c_{ec} : 0.115 to 0.145
- c_{cr} : 0.019 to 0.021



Explore with us

I-35/I-80 at Walnut Creek

I-35 SB / I-80 WB (red)

- Negligible grade changes across existing roadway, up to 17 feet of fill along the existing side slopes

I-35 NB / I-80 EB (green)

- Negligible grade changes across existing roadway, up to 14 feet of fill along the existing side slopes



Explore with us

I-35/I-80 at Walnut Creek

I-35 SB / I-80 WB (red)

- Drag loads on bridge piles
- Settlement of approach pavements
- Global slope instability and inadequate bearing resistance below retaining Wall C


I-35 NB / I-80 EB (green)

- Drag loads on bridge piles
- Settlement of approach pavements
- Global slope instability and inadequate bearing resistance below retaining Wall B



Explore with us

I-35 / I-80 at Walnut Creek Soils Remediation



I-35 / I-80 at Walnut Creek Specified Construction Sequence

- Bench existing roadway embankment



Explore with us

I-35 / I-80 at Walnut Creek Specified Construction Sequence

- Bench existing roadway embankment
- Install IFIs



Explore with us

I-35 / I-80 at Walnut Creek Specified Construction Sequence

- Bench existing roadway embankment
- Install IFIs
- Install settlement plates



Explore with us

I-35 / I-80 at Walnut Creek Specified Construction Sequence

- Bench existing roadway embankment
- Install IFIs
- Install settlement plates
- Place moisture control fill (embankment-in-place)



Explore with us

I-35 / I-80 at Walnut Creek Specified Construction Sequence

- Bench existing roadway embankment
- Install IFIs
- Install settlement plates
- Place moisture control fill (embankment-in-place)
- Construction delay for monitoring




Explore with us

I-35 / I-80 at Walnut Creek Specified Construction Sequence

- Bench existing roadway embankment
- Install IFIs
- Install settlement plates
- Place moisture control fill (embankment-in-place)
- Construction delay for monitoring
- Install abutment piles, then proceed with typical sequencing



Explore with us



Pedestrian Trail Over Exit Ramp A




Explore with us

Pedestrian Trail Over Exit Ramp A

Glacial Clays

- Slightly 'better' than the alluvial clays at Walnut Creek



Explore with us

Pedestrian Trail Over Exit Ramp A

West Abutment

- Up to 10 feet of fill

East Abutment

- Up to 15 feet of fill



Explore with us

Pedestrian Trail Over Exit Ramp A

West Abutment


- Drag loads on bridge piles
- Settlement of trail at bridge abutment


East Abutment


- Drag loads on bridge piles
- Settlement of trail at bridge abutment
- Inadequate bearing resistance below retaining Wall A1



Explore with us







I-35/I-80 at Hickman Road

Explore with us

I-35 SB/I-80 WB at Hickman Road

Glacial Clays

- Even 'better' than the glacial clays at the Pedestrian Bridge

Explore with us

I-35 NB/I-80 EB at Hickman Road

Glacial Clays

- Even 'better' than the glacial clays at the Pedestrian Bridge

Explore with us

24

I-35/I-80 at Hickman Road

I-35 SB / I-80 WB (red)

- Fills of 4-6 feet across the existing roadway, 12-13 feet along embankment slopes

I-35 NB / I-80 EB (green)

- Fills of 4-6 feet across the existing roadway, 13-15 feet along embankment slopes

Explore with us

I-35/I-80 at Hickman Road

I-35 SB / I-80 WB (red)

- Global slope instability and inadequate bearing resistance below retaining walls

I-35 NB / I-80 EB (green)

- Global slope instability and inadequate bearing resistance below retaining walls

Explore with us

I-35/I-80 at Hickman Road


I-35 SB / I-80 WB (red)

- Global slope instability and inadequate bearing resistance below retaining walls

I-35 NB / I-80 EB (green)

- Global slope instability and inadequate bearing resistance below retaining walls

Explore with us



Geotechnical Challenges I-35/80 & Hickman Road Interchange

- Project successes
 - Geotechnical challenges usually have more than one solution, we started those discussions early in project development



Explore with us

Geotechnical Challenges I-35/80 & Hickman Road Interchange


- Project successes
 - Geotechnical challenges usually have more than one solution, we started those discussions early in project development
 - Not all soils-related challenges need to be solved with a geotechnical solution, we also considered structural solutions or a design change



Explore with us

Geotechnical Challenges I-35/80 & Hickman Road Interchange

- Project successes
 - Geotechnical challenges usually have more than one solution, we started those discussions early in project development
 - Not all soils-related challenges need to be solved with a geotechnical solution, we also considered structural solutions or a design change
 - Ultimately, our 'best' solutions were the ones that fit within the space constraints, supported the construction sequencing and schedule, and had the least cost impact


 Explore with us

Thank you!

Contacts


Matthew D. Cushman, P.E.
Senior Engineer
D (515) 557 3827
Matthew.Cushman@terracon.com


Zach Bonzer, P.E.
Iowa Transportation Lead – Geotechnical
D (515) 557 3825
Zach.Bonzer@terracon.com



I-35/80 & US-6 (Hickman Road) Signing / ITS / Lighting

GARRET MENARD






September 26, 2025



The Stats (265)


- 13 Sign Trusses (3 Modified)
- 2 Sign Mastarms
- 104 Type 'A' Signs
- 53 Type 'B' Signs
- \$5.5 Million Bid (Hawkins)
 - \$7.1M estimated
 - 3 other bids around \$8M



HDR

Staging

- 7 Interstate Stages, 3 Hickman Road Stages
- Scroll Plots, Supplemental 100 Scale Sheets



HDR

[illegible]

Modified Barrier (2 Sign Trusses)

The drawing illustrates the design of a Modified Barrier (2 Sign Trusses). The plan view shows a 100-foot long barrier with various components including sign trusses, concrete panels, and drainage. The cross-sections (A-A, B-B, C-C, D-D) show the barrier's profile and dimensions.

Cross-Section Dimensions:

- SECTION A-A:** 10' height, 10' width at base, 10' width at top.
- SECTION B-B:** 10' height, 10' width at base, 10' width at top.
- SECTION C-C:** 10' height, 10' width at base, 10' width at top.
- SECTION D-D:** 10' height, 10' width at base, 10' width at top.

Latest Modified Barrier (based on Zone of Intrusion)

The Stats (270)

- 2 Modified Sign Trusses
- 17 Type 'A' Signs
- 3 Type 'B' Signs
- 3 Overlay Sign
- \$1.2 Million Bid (Cramer & Assoc.)
 - \$950k Estimate
 - 1 other \$1.3M Bid



HR

Staging


- 5 Interstate Stages



HR

Modified Sign Trusses

- 2 Modified Sign Trusses for Large DMS (100')



HR

Future Work (275)

- 2 Potential Arterial DMS along Hickman Road
- DDI Signage
- Signs Attached to Bridge



Fig. 2D-21. Example of Transposed Alignment Crossroad Guide Signing at Diamond Interchange from MUTCD


HR

2

ITS

The Stats (310)

- 17,010 feet of fiber
- 31 handholes
- 3 ITS cameras on poles (2 with sensors)
- 4 cabinets (1 for DMS)
- 312 splices
- \$610k Bid (Hawkins)



HR


The Stats (359)

- 5,130 feet of fiber
- 25 handholes
- 2 ITS cameras on trusses
- 3 sensors on trusses
- 5 cabinets (2 for DMS)
- 48 splices
- \$435k Bid (United or Cramer)



HR

Staging



HR

Future Work

- Potential addition of 2 arterial DMS



HR

3

INTERSTATE LIGHTING

Existing Interstate Lighting

- The I-80/I-35 interchange south of University Avenue is illuminated with high mast lighting.
- I-35 north of Douglas Avenue is illuminated with conventional light poles.
- Dark stretch of interstate between University Avenue and Douglas Avenue.



HR

Proposed Lighting

- Continuous interstate lighting to be installed between University Avenue and Douglas Avenue
- Light poles to be installed along the interstate and ramps.
- No high mast tower lighting units will be utilized



HR

Design Considerations

- No light poles in the medians
 - Narrow median barrier section
 - Minimize interaction with sign trusses and storm sewers
 - Would require boring power feeds to the median under live traffic
- Light poles placed along roadway shoulder
 - Improves constructability and maintenance
 - Increased use of luminaires with wide light distribution (Type IV)
 - Required special retaining wall blister design



HDR

Construction

- 150 light poles



HDR

DISCUSSION & QUESTIONS





Number Facts

\$ 107.4 Million (Awarded)
Approx. \$87 million for July '24 Letting
Approx. \$20 million for July '25 Letting

\$ 13.3 Million (Programmed)
One more project will be let for completion

There are 13 different projects on this contract

There are 37 funding categories between the 13 projects

There are 6 Stages & 7 Sites!

Interesting Facts

Amount of Dirt: 382,858.0 CY
Amount of Concrete: \$1,252.63 CY
Amount of Steel: 4,568,195.0 LB

Contract Information

Initial Bid: \$87,428,012.02
Average Bi-Weekly Voucher: \$2.5 Mil.
Total Number of Items: 730

WOW!

Contractor & Subcontractors

There are currently 25 subcontractors working under the Prime

UNITED CONTRACTORS

ABAC CONSULTING
CTI
ELDER
COMMUNICATION INNOVATORS

Gus Construction Co. Inc.
Dave Gryp Construction, Inc.
CONCRETE CUTTING CO.
DCC
DM2
precision
Iowa Signal Inc

BRAUN INTERTEC
VOLTAIR
THE DRILLER
INROADS
ABSOLUTE GROUP

Iron Works, Inc.
LINDNER
KELLER
ADVANCED

[illegible]

Walnut Creek

Multiple issues were discovered when placing steel for the WB Walnut Creek Bridge



Deck Pour



Intermediate Diaphragm Connection



Overhang Brackets



Finishing Operations



Finishing Machine Rail

IOWA DOT

124

The Raccoon Disaster



In May 2025, a raccoon caused a piece of heavy equipment to break down.

Repairs took several thousands of dollars, and approx. 1 month of time



IOWA DOT

125


Weather



From mid-June, there was 13 days charged to the project

IOWA DOT

126






Questions?

Frank Leong, P.E.
Grimes Construction Office
515-986-2850
frank.leong@iowadot.us


PLEASE DRIVE CAREFULLY

Thank you!




SNYDER
ASSOCIATES

Nathan Carhoff
515-864-1882
ncarhoff@snyder-associates.com
snyder-associates.com




Terracon

Matthew Cushman
515-557-3827
matthew.cushman@terracon.com
terracon.com



HDR

Garret Menard
402-399-1350
garret.menard@hdrinc.com
hdrinc.com



IOWA | DOT

Frank Leong
515-986-2850
frank.leong@iowadot.us
iowadot.gov
